

Temporary Electrical Installation Risk Assessment
prepared by Pete Wintercrane on behalf Bigtopmania

viz/ marquee hire operations.
viz/ entertainment activities.
viz/ electrical kit hire and use.
viz/ electricity at work
viz/ electrical installation work

NB;

No formal pre-prepared risk assessment replaces the constant updating and decision making process being made by workers on the ground. Dynamic risk assessment is preferred by both management, sub contractors & workers.

NB: most of our own installations work invariably falls

under the scope of section 5 of BS7909.

"Small /Simple events and activities requiring up to 6KVA". then follow

Section 6 "large/complex events and activities requiring in excess 6kva"

To be read and adhered to in addition to guidelines./ references including; (non exhaustive nor exclusive).

(nb; Much more guidance and Reg's info' available at HSE, BSI ,the IEE & the Electrical Safety Council with constant updates available.)

The Health and Safety at Work Act 1974 / manual handling regs/ Working at Height regs/ Noise Reduction regs.

Management of Health and Safety at Work Regs. 1992

Electricity at Work Regs 1989

P.U.W.E.R & L.O.L.E.R regs.

BS 7671: 2008 IEE 17 the Edition Wiring Regulations; Requirements for Electrical Installations

IEE 3rd ed.Code of Practice for Inservice Inspection and Testing Electrical Equipment.

IEE BS 7671: 2008. On Site Guide.

Bs; 7909:2008 Code of Practice for temporary electrical systems for entertainment and related purposes.

HSE; 2004. Maintaining Portable and Transportable electrical Equipment

HSE:1997. Electrical Safety at Places of Entertainment

HSE; 2003. Electricity at Work; safe working practices

HSE; 1996; Maintaining portable electrical equipment in offices and other low risk environments

HSE:1997. Electrical Safety for Entertainers

HSE; 1999. The Event Safety Guide.

HAE, EST 2012. Guidance on Electrical Safety Testing in the Hire industry, code of practice.

IET Guidance note 3 Inspection and Testing.

Un-Safe Working Practices / kit

may cause fatalities or serious injury to employees, sub contractor, other workers and general public.

NB> ELECTRICITY IS INHERENTLY DANGEROUS

Work is only to be done according to competence and training, above which level it is unsafe & permissible to not do the work. The More suitable, currently qualified persons are to undertake this work.

Most Installations should be tested and results recorded pre use.

notes on calculation of risk

no injury
minor injury
reportable injury
major injury
fatality

severity

1
2
3
4
5

Determination of action

probability

improbable 1
remote 2
possible 3
probable 4
likely 5

risk rating

severity

x probability

risk level

Priority

1-5
6-10
11-15
16-25

Action ?

No action needed
If reasonably practical
Must take action
Must take action

GENERAL RISKS: general work methods.

Identifiable

Hazard / Risk

slip and trip
bending and lifting
i.e.; Manual Handling

Equipment.

Place of Work

location of activity

electric

fire

Presence of General Public or working with children and persons with special needs animals

Training for equipment use/work

Worker unfit/unsuitable/un-trained/ incorrectly dressed for activity

Persons

at risk

all

safety tool-box-talks before work activity starts re; personal responsibility for health and safety, welfare of self and others, objectives, methods, responsibilities etc.. try to keep working area tidy and constant awareness.

all

pre-activity checks and regular maintenance equipment suitable for needs.

all

ensure suitable location and check safe before commencing

all

vocational risk assessment undertaken by organisers

all

Vocational maintenance undertaken by management.

all

sufficient space for activity to happen safely.

all

Ideally work in public free zone. adhere to national guidelines & staff are police checked. experienced and qualified staff be aware of animals and keep separate, watch for rodent attack on cables etc.

all

Ensure adequate training/how to use safely and correctly and highlight that accidents can be caused by inappropriate behaviour. only work to levels personal competency

all

Training/ Use of PPE; work skills appropriate to the participant advise suitable work footwear and clothing

Event Manager for most installations; Client or Pete Wintercrane

Senior Person Responsible for most temporary electrical installations; Pete Wintercrane

Responsible Person for small installations; tent master/ foreman

Specific Risks Associated with Electrical Safety

Temporary Electrical Installations

Risk Level

Severity

Possibility

Risk

ACTION

<u>Operations and activities</u>		<u>and use of equipment</u>				<u>Rating</u>	
<u>Identifiable HAZARD covering provision, setting up, operation and removal of system</u>	<u>Identifiable Harm</u>	<u>Persons at risk</u>	<u>Control Measures and Safeguards</u>				
Electric shock from "build" equipment whilst working with it. e.g.; drills, power saws, catering equipment, computers. Work lights	shock ranging minor to death other injury, burns, fire	workers. others.	Ensure Power supply/ Installed System is safe and with RCD. Visually inspect pre-use and follow safe working practices. Use 110 v equipment where possible. Maintain and test equipment regularly according to regs., Only competent people to do such work.	medium. high 5	5	15	MUST FOLLOW SAFEGUARDS> competent worker ensure use correct equipment ensure use of PPE. follow regs. inherent danger if not followed.
Installation /removal of Temporary Electrical Equipment	shock ranging minor to death	workers. installers crew	Follow safe working practices. inc' de-energising system. plan well and follow design. Think!				
e.g.; cables, lighting, sockets, pa systems, heating systems,	manual handling, trip hazards. working at height cuts, burns, fire.	others. installers artists public	Pre-Plan & ensure power supply is safe & sufficient & equipment appropriate . Only competent people to do work. Maintenance and inspection of kit as above. Ensure kit installed safely, leaving no identifiable extra hazards. e.g. use RCD's safe cable runs, safety chains when rigged at height. Ensure correct earthing and bonding, take care with metal work and fittings. Only connect Live when fully satisfied safe system. Record findings.	medium high 5	3	15	as above
Use of installed electrics and kit. e.g. before, during and after an event	shock, burn, fire, trip,	public. workers. artists.	test and ensure the system is installed safely. Use marquee hire checklist/ electric system sign off sheets. Visually check again before use/ constant vigilance and checking. Energise in sequence awareness of extra items/ changes to circuits changed. Only competent people to use kit and no tampering/ changes advised. Advise key people of risks./inform responsible person about the install requirements and how to use safely. Do not leave unattended or without a responsible person. try and keep cables and items out of public reach or routes.	medium/ high 5	3	15	as above
Other persons or companies electrical kit	shock ranging minor to death	all	Other persons kit must be similarly safe, tested and installed correctly.	medium	5	3	15 as above
weather conditions	can affect safe install, use and removal as well as the kit itself		monitor weather and forecasts. Adapt install accordingly if needed ensure correct IP ratings and weather protection/ shield from sun	medium	5	4	20 as above
the effects of any lighting installed on nearby traffic routes	eg drivers could be affected by glare all or attention diverted by lighting effects	all	avoid pointing lights at traffic routes. event signage? avoid flashes.	low	5	3	15 as above
time of day	will affect the power requirements and public/ staff presence	all	plan and expect variation in demands	low	3	3	9 as above
hazardous environments , eg mines, petrol stations, flammable dust, explosive materials	fire, explosion, flammable material. unsafe working / install/ removal/ use	all	check in planning stages and avoid if possible	high if present	5	2	10 as above
Presence of water	may affect IP ratings, earthing, bonding slip hazards. shock hazard failure of system	all	keep an eye on effects and ponding locations avoid laying cables or kit in possible water runs. be aware of drips from tent roof and where kit is then installed. be aware of equipment ratings and location be aware of expected wet areas, eg bars, exterior lighting	medium	3	3	15 as above
length of time the system is needed	may affect system safety and equipment security	all	ensure a plan in place for system safety and security. Daily visual tests. there should be a competent person present during use, check regularly.	medium	5	3	15 as above
possible mutual EMI effects between temporary and permanent systems	may affect planned results and interfere with installed system and earthing	all	plan correctly to try and avoid.	medium	5	3	15 as above
removal of system	shock. manual handling, trip hazards. working at height cuts, burns, fire.	all	ensure system is dead before work commences, visually check items. de energise in sequence perhaps leave work lights on if dark check each item as removed and packed. remove and label any suspect items for further inspection.	low to medium5 if de energised.		3	15 as above